IB APPROVED SEPARATION SHEET

IB MEMBRANE

MEMBRANE TERMINATION AT WALL AND 2ND FIELD COURSE FASTENED PER TABLE A.9 WITH IB #15 FASTENER AND 2-3/8" BARBED PLATES (SEE NOTE 5)

HOT AIR WELD

67"

5"

18" MAX.
(SEE MECHANICALLY ATTACHED TALL WALL DETAIL)

INSULATION ASSEMBLY

ROOF DECK

NOTES:
1.   SINGLE COURSE BASE / WALL FLASHING MAXIMUM HEIGHTS:
   A. 18" FOR MECHANICALLY ATTACHED FLASHINGS
   B. FOR WALLS EXCEEDING MAXIMUM HEIGHTS, REFER TO MECHANICALLY ATTACHED TALL WALL DETAILS.
2.   SECURE FLASHINGS AND METAL WORK IN ACCORDANCE WITH IB SPECIFICATIONS AND FLASHING SECUREMENT TABLE.
3.   SEALANTS AND CAULKING REQUIRE PERIODIC OWNER MAINTENANCE.
4.   REFER TO FT AND/OR PT DETAILS FOR APPROVED FLASHING AND PARAPET WALL TERMINATIONS
5.   REFER TO TABLE A.9 FOR FASTENING SCHEDULE AND DETAIL WD-12 FOR ALTERNATE MEMBRANE TERMINATION AT WALL
APPROVED SUBSTRATE / SEPARATION:
NEW CONSTRUCTION - MECHANICALLY ATTACHED
   ·   1/2" PLYWOOD, 7/16" OSB, 1/2" APPROVED GYPSUM COVER BOARD, POURED / PRECAST CONCRETE, OR CEMENT BLOCK /
       MASONRY WALLS.
MECHANICALLY ATTACHED RECOVER OVER APPROVED EXISTING WALL AND BASE FLASHINGS
   ·   FULL SEPARATION REQUIRED WITH MINIMUM 1/2" PLYWOOD, 1/4" APPROVED GYPSUM COVER BOARD, 7/16" OSB, OR APPROVED
       IB SEPARATION SHEET.

Scale: NTS	Detail Name: Membrane Termination at Wall for Full Sheet Layout	Detail Number: WD - 11
Submitted By: Address: Telephone:	Project: Address:	